



**GENERAL NOTES:**

1. Replace roof with new 60 mil. direct adhered membrane roof. Remove existing roofs to concrete deck.
2. Replace Roof Drains. Provide new drains with metal grate.
3. Existing Metal Ladders - scrape and repaint with primer and two coats rust-inhibiting enamel paint. Reanchor loose bolts.
4. Replace metal coping with new terne-coated stainless metal\_\_\_\_\_.
5. Existing limestone coping. Clean, remove existing caulk and recaulk using Somabome NP-1 or equal.
6. Replace existing metal gravel stop.
7. Provide new drip edge, gutter and downspouts to match existing. Provide splash block at downspout discharge.
8. Existing roof fan.
9. HVAC Cooling tower. Paint metal support structure with
10. Parapet Wall. Cover with roofing material adhered to wall.
11. New Gutter and Downspouts.
12. Existing 4 inch roof vent.
13. Existing structure under roof. Continue roofing over structure below.
14. Replace existing scupper thru wall. Add new boot and downspout to roof below with splashblock.

BUILDING 25 - ROOF PLAN  
PARKERSBURG, WV