BRONZE WINDOW REPAIR CODES

GENERAL (CAN APPLY TO ALL WINDOW COMPONENTS)
A – PREPARE SURFACE AND REFINISH ASSEMBLY
B – REMOVE INTERIOR PAINT COATING
C – FILL HOLE (#)
D – REMOVE SCREW & PATCH HOLE (#)
E – REPLACE MISSING BRASS OR EXISTING FERROUS SCREWS WITH NEW BRASS SCREWS (#)

FRAME
F – ACCESS, CLEAN & LUBRICATE PULLEYS & SASH WEIGHTS
G – REMOVE STORM WINDOW ASSEMBLY
H – REPAIR CRUSHED SILL
J – REMOVE STEEL CHANNEL FROM EXTERIOR AND PATCH HOLES
K – REMOVE, RESTORE & REINSTALL GRILLES

SASH
L – REMOVE, CLEAN, REINSTALL & MAKE SASH FULLY OPERATIONAL
M – REPLACE MISSING OR BROKEN SASH CHAIN (#)
N – REPLACE MISSING OR BROKEN SASH LOCK
P – REPLACE MISSING OR BROKEN SASH LIFT (#)
Q – REPLACE MISSING OR BROKEN SASH HOOK (#)
R – REPLACE MISSING OR BROKEN MUNTIN BAR (#)

GLAZING
T – REPLACE MISSING OR BROKEN CLEAR GLASS PANE (#)
U – REPLACE MISSING, BROKEN OR NON-ORIGINAL OBSCURE GLASS PANE (#)
V – REMOVE ALL DETERIORATED GLAZING PUTTY AND REPLACE WITH NEW AT ALL PANES
W– REMOVE ALL DETERIORATED GLAZING PUTTY AND REPLACE WITH NEW AT ALL ADDITIONAL PANES NOT INCLUDED IN BASE BID (ALTERNATE #1)

NOTES
X – ACCESS PARTIALLY OBSTRUCTED BY RADIATOR COVERS
Y – CLEAN CASEMENT IN SITU W/ NON-IONIC DETERGENT
Z – ACCESS, CLEAN & LUBRICATE CASEMENT HARDWARE
AA – COORDINATE ACCESS & REMOVAL WITH GSD AND SECURITY DETAIL

MAIN BUILDING - COLONNADE LEVEL (EXTERIOR CASEMENTS ONLY)

WINDOW	TYPE	FRAME SIZE WIDTH	FRAME SIZE HEIGHT	REFERENCE	REPAIR GENERAL	REPAIR FRAME	REPAIR SASH	REPAIR GLAZING
6001	H	4'-10"	20'-0"	8/A-700	Y	–	–	–
6002	H	4'-10"	20'-0"	8/A-700	Y	–	–	–
6003	H	4'-10"	20'-0"	8/A-700	Y	–	–	–
6004	H	4'-10"	20'-0"	8/A-700	E(1),Y	–	–	–
6005	H	4'-10"	20'-0"	8/A-700	Y	–	–	–
6006	H	4'-10"	20'-0"	8/A-700	Y	–	–	–
6007	H	4'-10"	20'-0"	8/A-700	Y	–	–	–
6008	H	4'-10"	20'-0"	8/A-700	Y	–	–	–
6009	H	4'-10"	20'-0"	8/A-700	Y	–	–	–
6010	H	4'-10"	20'-0"	8/A-700	Y	–	–	–
6011	H	4'-10"	20'-0"	8/A-700	Y	–	–	–
6012	H	4'-10"	20'-0"	8/A-700	Y	–	–	–
6013	H	4'-10"	20'-0"	8/A-700	Y	–	–	–
6014	H	4'-10"	20'-0"	8/A-700	Y	–	–	–
6015	H	4'-10"	20'-0"	8/A-700	Y	–	–	–
6016	H	4'-10"	20'-0"	8/A-700	Y	–	–	–

MAIN BUILDING - BALUSTRADE LEVEL

WINDOW	TYPE	FRAME SIZE WIDTH	FRAME SIZE HEIGHT	REFERENCE	REPAIR GENERAL	REPAIR FRAME	REPAIR SASH	REPAIR GLAZING
7001	I	3'-0"	3'-0"	9/A-700	Y	–	–	–

SWANKE HAYDEN CONNELL ARCHITECTS

Swanke Hayden Connell Ltd.
Swanke Hayden Connell & Partners, LLP
295 Lafayette Street, New York, New York 10012
Phone 212 226 9696, Fax 212 219 0059

Structural Engineer:
CAS Structural Engineering, Inc.
P.O. Box 469
Alum Creek, WV 25003

Metal Conservator:
Kreilick Conservation, LLC
519 Toll Road
Oreland PA 19075

It is a violation of the law to alter this document in hard copy or electronic format (the "document") in any way. Use or modifications to this document is at the sole risk and liability of the user. The user shall, to the fullest extent of the law, hold SHCA harmless from any claims, liabilities or damages including legal fees that may be incurred as a result of any unauthorized or improper use or modification of this document.

Key Plan



NORTH

No:	Date:	Revision:
–	06-08-07	ISSUED FOR BID
–	07-06-07	ISSUED FOR RE-BID
1	09-27-07	ADDENDUM #4

STATE OF WEST VIRGINIA
DEPARTMENT OF ADMINISTRATION — DIVISION OF GENERAL SERVICES
CHARLESTON, WEST VIRGINIA

LOCATION: **Charleston, West Virginia**
BUILDING: **West Virginia State Capitol**
PROJECT: SHCA PROJ. #: 5827-D **Masonry Cleaning & Repair Project**
DRAWING TITLE: **Window Schedule Dome**
DRAWING NO: **A-705**
DRAWN BY:
SCALE:
DATE: 06-08-07

ALL INFORMATION ON THIS DOCUMENT IS PROPERTY OF THE STATE OF WEST VIRGINIA AND SHALL NOT BE REPRODUCED OR EXHIBITED TO OTHERS, IN WHOLE OR IN PART, WITHOUT THE EXPRESS WRITTEN CONSENT OF THE STATE OF WEST VIRGINIA.

CAD FILE SOURCE:
C:\ACAD\SUPPORT\SHEETS\D-SHEET

2007/09/28 W:\5827\D\DWG\03CD\PLOT\ADDENDUM #4\A-705_WINDOW SCHEDULE_DOME_ADD#4.DWG
W:\5827\D\Dwg\03CD\PLOT\Addendum #4\A-705_window schedule_dome_ADD#4.dwg 9/28/2007 11:03:19 AM JOHNSON,S