

VENDOR

RFQ COPY

TYPE NAME/ADDRESS HERE

State of West Virginia Department of Administration Purchasing Division 2019 Washington Street East Post Office Box 50130 Charleston, WV 25305-0130

Request for Quotation

SMC00268

PA	GÉ	
	1	

ADDRESS CORRESPONDENCE TO ATTENTION OF

JOHN ABBOTT 304-558-2544

304-558

T

DIVISION OF CORRECTIONS ST. MARYS CORRECTIONAL CENTER

2880 N PLEASANTS HWY ST. MARYS, WV 26170 304-

304-684-5500

DATE PRIN	TED	TER	MS OF SAL	É	SH	IP VIA			о.в.		FREIGHT TERMS
01/13/	2009				haganaranaran kutuki daga bigi		20000000	<u>6.19646.000.0000.5</u>			
BID OPENING DATE:		02/12/	2009		<u></u>	RID	UDE	NTNC	TIME	0.1	:30PM
LINE	QUAN		UOP	CAT	17 F K 4 1					. U .	
LINE	GUAN	JH t	OOP	NO.	II EMI	NUMBER		UNI	TPRICE		AMOUNT
0001	FUEL S	1	LS CONT	.]	100-30 NT BARR:	IER INSTA	ALLA	TION			
	CONTRAC MENT NI BARRIEI MARYS,	CT TO ECESSA R AT T WV, P	PROVI RY TO HE ST ER TH	DE AL INST . MAR E SPE	L LABOR, ALL A FU YS CORRE CIFICAT]	MATERIA JEL STORA CCTIONAL	ALS, AGE CEN	AND CONTA	INME	9- NT	
	MANDATO	DRY ON	SITE	PRE-B	ST. 2880	27/09; 10 MARYS CO N. PLEA MARYS, W	RRE SAN	CTION TS HW		ITR.	
	CONTACT	TON		ASTER		T DON SP 684-5500					
:	EXHIBIT	Г 5	1	i							
	TION FOR REQUIRE SUBMIT THE BID SIGNED VENDOR'CHAPTER MIT THE RESULT	OR A PRESENTED AT THE AT THE AND SECOME SECO	JBLIC H VENE E SAME E ENCL JBMIT PLIANC THE ED PUE SQUAL	IMPRODOR THE TIME OSED WITH THE TOTAL THE	OVEMENT HAT SUBME AN AFF PURCHAS ITH THE ITH THE P VIRGINI ING AFFI ION OF	VIDES TH CONSTRUC ITS A BI IDAVIT O ING AFFI BID AS E ROVISION A CODE. DAVIT WI SUCH BID ACT IS T THE NOTI	TIO D F DAV VIDI S OI FA TH	N CONDR THOMPLI IT MUENCE ART ILURE THE B	TRACT E WOR ANCE ST BE OF TH ICLE TO S ID SH	K TO WITH E 1D, UB- ALL	
				SEE REVI	ERSE SIDE FOR	TERMS AND CON	I NDITION	ıs			
IGNATURE			**************************************			TELEPHONE			<u></u>	DATE	
ITLE		FEI		, ,			<u> </u>	ADDI	RESS CH	ANGES 1	TO BE NOTED ABOVE

GENERAL TERMS & CONDITIONS REQUEST FOR QUOTATION (RFQ) AND REQUEST FOR PROPOSAL (RFP)

- 1. Awards will be made in the best interest of the State of West Virginia.
- 2. The State may accept or reject in part, or in whole, any bid.
- 3. All quotations are governed by the West Virginia Code and the Legislative Rules of the Purchasing Division.
- 4. Prior to any award, the apparent successful vendor must be properly registered with the Purchasing Division and have paid the required \$125 fee.
- 5. All services performed or goods delivered under State Purchase Order/Contracts are to be continued for the term of the Purchase Order/Contracts, contingent upon funds being appropriated by the Legislature or otherwise being made available. In the event funds are not appropriated or otherwise available for these services or goods, this Purchase Order/Contract becomes void and of no effect after June 30.
- 6. Payment may only be made after the delivery and acceptance of goods or services.
- 7. Interest may be paid for late payment in accordance with the West Virginia Code.
- 8. Vendor preference will be granted upon written request in accordance with the West Virginia Code.
- 9. The State of West Virginia is exempt from federal and state taxes and will not pay or reimburse such taxes.
- 10. The Director of Purchasing may cancel any Purchase Order/Contract upon 30 days written notice to the seller.
- 11. The laws of the State of West Virginia and the *Legislative Rules* of the Purchasing Division shall govern all rights and duties under the Contract, including without limitation the validity of this Purchase Order/Contract.
- 12. Any reference to automatic renewal is hereby deleted. The Contract may be renewed only upon mutual written agreement of the parties.
- 13. BANKRUPTCY: In the event the vendor/contractor files for bankruptcy protection, this Contract may be deemed null and void, and terminated without further order.
- 14. HIPAA BUSINESS ASSOCIATE ADDENDUM: The West Virginia State Government HIPAA Business Associate Addendum (BAA), approved by the Attorney General, and available online at the Purchasing Division's web site (http://www.state.wv.us/admin/purchase/vrc/hipaa.htm) is hereby made part of the agreement. Provided that, the Agency meets the definition of a Cover Entity (45 CFR §160.103) and will be disclosing Protected Health Information (45 CFR §160.103) to the vendor.
- 15. WEST VIRGINIA ALCOHOL & DRUG-FREE WORKPLACE ACT: If this Contract constitutes a public improvement construction contract as set forth in Article 1D, Chapter 21 of the West Virginia Code ("The West Virginia Alcohol and Drug-Free Workplace Act"), then the following language shall hereby become part of this Contract: "The contractor and its subcontractors shall implement and maintain a written drug-free workplace policy in compliance with the West Virginia Alcohol and Drug-Free Workplace Act, as set forth in Article 1D, Chapter 21 of the West Virginia Code. The contractor and its subcontractors shall provide a sworn statement in writing, under the penalties of perjury, that they maintain a valid drug-free work place policy in compliance with the West Virginia and Drug-Free Workplace Act. It is understood and agreed that this Contract shall be cancelled by the awarding authority if the Contractor: 1) Fails to implement its drug-free workplace policy; 2) Fails to provide information regarding implementation of the contractor's drug-free workplace policy at the request of the public authority; or 3) Provides to the public authority false information regarding the contractor's drug-free workplace policy."

INSTRUCTIONS TO BIDDERS

- 1. Use the quotation forms provided by the Purchasing Division.
- 2. SPECIFICATIONS: Items offered must be in compliance with the specifications. Any deviation from the specifications must be clearly indicated by the bidder. Alternates offered by the bidder as EQUAL to the specifications must be clearly defined. A bidder offering an alternate should attach complete specifications and literature to the bid. The Purchasing Division may waive minor deviations to specifications.
- 3. Complete all sections of the quotation form.
- 4. Unit prices shall prevail in case of discrepancy.
- 5. All quotations are considered F.O.B. destination unless alternate shipping terms are clearly identified in the quotation.
- 6. BID SUBMISSION: All quotations must be delivered by the bidder to the office listed below prior to the date and time of the bid opening. Failure of the bidder to deliver the quotations on time will result in bid disqualifications: Department of Administration, Purchasing Division, 2019 Washington Street East, P.O. Box 50130, Charleston, WV 25305-0130



VENDOR

RFQ COPY

TYPE NAME/ADDRESS HERE

State of West Virginia Department of Administration Purchasing Division 2019 Washington Street East Post Office Box 50130 Charleston, WV 25305-0130

Request for Quotation

SMC00268

REO NUMBER

33	333	PAG	E:
			_

ADDRESS CORRESPONDENCE TO ATTENTION OF

JOHN ABBOTT 304-558-2544

DIVISION OF CORRECTIONS ST. MARYS CORRECTIONAL CENTER

ADDRESS CHANGES TO BE NOTED ABOVE

2880 N PLEASANTS HWY ST. MARYS, WV 26170 304-684-5500

F.O.B. DATE PRINTED TERMS OF SALE SHIP VIA FREIGHTTERMS 01/13/2009 BID OPENING DATE: 02/12/2009 BID OPENING TIME 01:30PM LINE QUANTITY UOP ITEM NUMBER UNIT PRICE AMOUNT IS RECEIVED. UNLESS OTHERWISE SPECIFIED, THE FULLY EXECUTED PURCHASE ORDER WILL BE CONSIDERED NOTICE TO PROCEED. THE DIRECTOR OF PURCHASING RESERVES THE CANCELLATION: RIGHT TO CANCEL THIS CONTRACT IMMEDIATELY UPON WRITTEN NOTICE TO THE VENDOR IF THE MATERIALS OR WORKMANSHIP SUPPLIED ARE OF AN INFERIOR QUALITY OR DO NOT CONFORM WITH THE SPECIFICATIONS OF THE BID AND CONTRACT HERE IN. WAGE RATES: THE CONTRACTOR OR SUBCONTRACTOR SHALL PAY THE HIGHER OF THE U.S. DEPARTMENT OF LABOR MINIMUM WAGE RATES AS ESTABLISHED FOR PLEASANTS COUNTY, PURSUANT TO WEST VIRGINIA CODE 21-5A, ET, SEQ. (PREVAILING WAGE RATES APPLY TO THIS PROJECT) ANY REFERENCES MADE TO ARBITRATION OR ARBITRATION: INTEREST FOR PAYMENTS DUE (EXCEPT FOR ANY INTEREST REQUIRED BY STATE LAW) CONTAINED IN THIS CONTRACT OR IN ANY AMERICAN INSTITUTE OF ARCHITECTS DOCUMENTS PERTAINING TO THIS CONTRACT ARE HEREBY DELETED. WORKERS' COMPENSATION: VENDOR IS REQUIRED TO PROVIDE A CERTIFICATE FROM WORKERS' COMPENSATION IF SUCCESSFUL. ALL OF THE ITEMS CHECKED BELOW WILL BE A REQUIREMENT OF THIS CONTRACT: (XX) INSURANCE: SUCCESSFUL VENDOR SHALL FURNISH PROOF OF COMMERCIAL GENERAL LIABILITY INSURANCE PRIOR TO ISSUANCE OF CONTRACT. UNLESS OTHERWISE SPECIFIED IN THE BID DOCUMENTS, THE MINIMUM AMOUNT OF INSURANCE COVERAGE REQUIRED IS \$250,000.) BUILDERS RISK INSURANCE: SUCCESSFUL VENDOR SHALL SEE REVERSE SIDE FOR TERMS AND CONDITIONS SIGNATURE TELEPHONE DATE



DOCER

RFQ COPY

TYPE NAME/ADDRESS HERE

State of West Virginia Department of Administration Purchasing Division 2019 Washington Street East Post Office Box 50130 Charleston, WV 25305-0130

Request for Quotation

SMC00268

ADDRESS CORRESPONDENCE TO ATTENTION OF

JOHN ABBOTT 304-558-2544

DIVISION OF CORRECTIONS ST. MARYS CORRECTIONAL CENTER

2880 N PLEASANTS HWY ST. MARYS, WV 26170

304-684-5500

DATE PRIN	TEĐ	TE	RMS OF SAI	LE	SI	RIV PIA		F.O.B.		FREIGHTTERMS
01/13/										
BID OPENING DATE:	450000000000000000000000000000000000000	02/12	/2009	location and a		BID	OPE	NING TIME	01	:30PM
LINE	QUAN	YTITY	UOP	CAT NO.	ITEM	NUMBER		UNIT PRICE		AMOUNT
	AN AMO (XX) B THE BI SUBMIT BIDDER MATERI BONDS IRREVO SOLVEN STATE IN LIE UNDER	UNT ENDONES: D PAYATED WITED W	FIVE ABLE T TH EA ALSO D FOR PROV LETTE TY CO T VIR BOND	BUILD D 100 PERC O THE CH BI FURN 100% IDED R OF MPANY GINIA WILL PERSO	% OF THE STATE DAS A ISH A POF THE IN THE CREDIT, AUTHOR ONLY B	E AMOUNT) OF THE OF WEST V BID BOND. ERFORMANC AMOUNT O FORM OF A OR BOND IZED TO D TTER OF C E ALLOWED BUSINESS	TOTA IRG: TIRG: E BO F TH CEFURN O BU CRED: CRED: CHEC	INSURANCE THE CONTRACT AL AMOUNT OF INIA, SHALL HE SUCCESSE DND AND LAR HE CONTRACT RTIFIED CHE VISHED BY A USINESS IN IT SUBMITTE R PROJECTS CKS ARE NOT	T. BE TUL BOR/ T. ECK, THE	
	BOND,	OR LAI AINTEN NG THE CCESSE	OR AN IANCE ROOF	D MAT BOND: ING S	ERIAL B A TWO	OND. (2) YEAR	MA	INTENANCE B JIREMENT OF		
	EXHIBI DOMEST PROJEC	IC ALU	MINUM	, GLA	SS & ST	EEL IN PU	BLIC	C WORKS	- Curing	
	SEQ., I ALTERA PUBLIC IN THE MORE TI	EVERY TION, WORKS CASE HAN \$5	CONTR REPAI , WHE OF ST 0,000	ACT F R, IM RE TH EEL O OR W D, TH	OR CONS PROVEME! E COST NLY, WHE HERE MO! E STATE	NT OR MAI IS MORE T ERE THE C RE THAN 1 WILL ACC	REC NTEN HAN OST 0,00 EPT	CONSTRUCTIONSTRUCTIONS OF STEEL IO POUNDS OONLY ALUMI	D, S F	
SIGNATURE				SEE REV	ERSE SIDE FO	R TERMS AND CON	NDITION		DATE	
0.0.410.42						TEEL HOIVE			ee4 ⊑	
TITLE		F	EIN					ADDRESS CHAI	NGES 1	O BE NOTED ABOVE



VEZDOR

RFQ COPY

TYPE NAME/ADDRESS HERE

State of West Virginia
Department of Administration
Purchasing Division
2019 Washington Street East
Post Office Box 50130 Charleston, WV 25305-0130

Request for Quotation

SMC00268

	F	Α	G	E	
				6	

ADDRESS CORRESPONDENCE TO A	TICALIDALIDE
ADDITION OF THE OF	CLICATION OF

JOHN ABBOTT 304-558-2544

DIVISION OF CORRECTIONS ST. MARYS CORRECTIONAL CENTER

2880 N PLEASANTS HWY ST. MARYS, WV 26170 304-684-5500

DATE PRINTED	TERMS	OFSALE	SHIP V	IA	F.C).B.	\$ 19 E	FREIGHT TERMS
01/13/2009								
BID OPENING DATE:	02/12/20			BID	OPENING	TIME	01	:30PM
GLASS, IN ADE FOR US DOMEST THE PR	OR STEEDITION, ISE AT THE	ITEMS OF SITE OF INUM, GLA SLESS TH	TEM NUM TS PRODUC MACHINERY PUBLIC W SS OR STEI AN \$50,00 ED IN PUB	ED IN T OR EQU ORKS SH EL, UNL O OR LE	UNITE IPMENT P ALL BE M ESS THE SS THAN	D STAT URCHAS ADE OF COST O	ES. ED	AMOUNT
FOREIG ACCEPT TO BE 20% OR PRODUC PRODUC LABOR DEPART ONLY I	N MADE A ED ONLY UNREASON MORE HI TS. IF TS TO BE SURPLUS MENT OF F DOMEST	ALUMINUM, IF THE C NABLE. SI GHER THA THE DOME SUPPLIE AREA", AS LABOR, FO	GLASS OR OST OF DOI UCH COST N THE BID STIC ALUM O OR PRODI S DEFINED OREIGN PRO CTS ARE 30	STEEL MESTIC IS UNRE PRICE INUM, G JCED IN BY THE DDUCTS OK OR M	PRODUCTS PRODUCTS ASONABLE FOR FORE LASS OR A "SUBS UNITED MAY BE S	MAY B IS FO IF IT IGN MA: STEEL TANTIA: STATES UPPLIE	UND IS DE L	
PROVIS DETERM ALUMIN THAN T OFFICE REDUCT ALL VE SUPPLY	IONS, THA INES THA UM, GLAS HE LOWES MAY REQ ION IN T NDORS MU ING FORE	IE SPENDING STEED OF	OF A CONT NG OFFICER EXISTS A I EL THAT IS MESTIC PRO WRITING, WRITING, BID FOR ATE IN THE	R OF THE BID FOR S REASO DUCTS, A REEV, SUCH DO EIR BID	E SPENDII LIKE FOI NABLE ANI THE SPEI ALUATION DMESTIC I IF THEY	NG UNI REIGN D LOWEI NDING AND PRODUC	₹	
	Т 9	A	CKNOWLEDG			RUCTION	1	
BIGNATURE	<u>,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,</u>			ELEPHONE		DA	ΤE	
TITLE	leens.							
ΠΤLË	FEIN				ADDR	ESS CHAN	GES 1	O BE NOTED ABOVE



A DOUGH

RFO COPY

TYPE NAME/ADDRESS HERE

State of West Virginia Department of Administration Purchasing Division 2019 Washington Street East Post Office Box 50130 Charleston, WV 25305-0130

Request for E Quotation

SMC00268

ADDRESS CORRESPONDENCE TO ATTENTION OF:

304-558-2544

JOHN ABBOTT

DIVISION OF CORRECTIONS ST. MARYS CORRECTIONAL CENTER

ADDRESS CHANGES TO BE NOTED ABOVE

2880 N PLEASANTS HWY ST. MARYS, WV 26170 304-684-5500

SHIP VIA F.O.B DATE PRINTED TERMS OF SALE FREIGHT TERMS 01/13/2009 BID OPENING DATE: BID OPENING TIME 02/12/2009 01:30PM UNIT PRICE **AMOUNT** LINE QUANTITY UOP ITEM NUMBER THE ARCHITECT/ENGINEER AND/OR AGENCY SHALL BE REQUIRED TO ABIDE BY THE FOLLOWING SCHEDULE IN ISSUING CONSTRUCTION PROJECT ADDENDA FOR STATE AGENCIES: THE ARCHITECT/ENGINEER SHALL PREPARE THE ADDENDUM AND A LIST OF ALL PARTIES THAT HAVE PROCURED DRAWINGS AND SPECIFICATIONS FOR THE PROJECT. THE ADDENDUM AND LIST SHALL BE FORWARDED TO THE BUYER IN THE STATE PURCHASING DIVISION. THE ARCHITECT/ENGINEER SHALL ALSO SEND A COPY OF THE ADDENDUM TO THE STATE AGENCY FOR WHICH THE CONTRACT IS ISSUED. THE BUYER SHALL SEND THE ADDENDUM TO ALL INTERESTED PARTIES AND, IF NECESSARY, EXTEND THE BID ANY ADDENDUM SHOULD BE RECEIVED BY THE OPENING DATE. BUYER WITHIN FOURTEEN (14) DAYS PRIOR TO THE BID OPENING DATE. ALL ADDENDA SHOULD BE FORMALLY ACKNOWLEDGED BY ALL (3) STATE BIDDERS AND SUBMITTED TO THE PURCHASING DIVISION. THE SAME RULES AND REGULATIONS BIDDING DOCUMENT ORIGINAL THAT APPLY TO THE SHALL ALSO APPLY TO AN ADDENDUM DOCUMENT. THE ONLY FOR AN ADDENDUM THAT IS ISSUED FOR TH EXCEPTION MAY BE SOLE PURPOSE OF CHANGING A BID OPENING TIME AND/OR DATE. REV. 11/96 EXHIBIT 10 ADDENDUM ACKNOWLEDGEMENT I HEREBY ACKNOWLEDGE RECEIPT OF THE FOLLOWING CHECKED AND HAVE MADE THE NECESSARY REVISIONS TO SEE REVERSE SIDE FOR TERMS AND CONDITIONS: TELEPHONE SIGNATURE

FEIN

TITLE



VENDOR

RFQ COPY

TYPE NAME/ADDRESS HERE

State of West Virginia
Department of Administration
Purchasing Division
2019 Washington Street East
Post Office Box 50130
Charleston, WV 25305-0130

Request for Quotation

SMC00268

	÷	: F	λ	G	E	ं	
_						_	
					6		

Δ	ADDRESS CORRESPONDENCE TO ATTENTION OF	Ö
JUNN	ABBOTT	
Z N // _ E	5 E Q _ 2 E / /	

SH-PTO

DIVISION OF CORRECTIONS ST. MARYS CORRECTIONAL CENTER

2880 N PLEASANTS HWY ST. MARYS, WV 26170 304-684-5500

DATE PRIN	TED	TER	MS OF SALE	SHII	² VIA	F.(O.B.	FREIGHT TERMS
01/13/								
BID OPENING DATE:		02/12/	2009		BID	OPENING	TIME 0	L:30PM
LINE	QUAN	ITITY	UOP CAT		UMBER	UNIT	T PRICE	AMOUNT
	(0.000-0.000000000000000000000000000000							
	MV PPO	DUCVI	DI ANC A	AD COR COM	TETCATIO	L ETO		
	in i ku	OSAL,	FLANS A	ND/OR SPEC	IFICATIO	N, EIL.		
	ADDEND	UM NOS	.:					
	1							
	NO. 1	•	• • • • • • • •					
	NO. 2	İ						
	NO. Z	•]	• • • • • • • • • • • • • • • • • • • •	• • • •				
	NO. 3							
	NO. 4	•	• • • • • • •	• • • •				
	NO. 5	:						
	NO. 5	•	• • • • • • • • • •			•		•
	I UNDE	RSTAND	THAT FA	LURE TO C	ONFIRM T	HE RECEI	PT OF THE	
	ADDENDI	JM(S)	MAY BE CA	USE FOR R	EJECTION	OF THE	BIDS.	
	VENDOD	MUST	DI CADIN I	WDED OT AUD				
				INDERSTAND IR ASSUMED				
				BETWEEN VI				
				EL IS NOT				
				WRITING A				
	SPECIF	CATIO	IS BY AN	OFFICIAL A	ADDENDUM	IS BIND	ING.	
				ļ				
					sı	GNATURE		
	• • • • • •	• • • • • • •	• • • • • • • •		col	MPANY		
		,			7.4	- -		
	• • • • • •	• • • • • • • • • • • • • • • • • • • •	• • • • • • • • • • • • • • • • • • • •	* * * * * * * * * * * * * * * * * * * *	DA	i E	3	
ı	REV. 11	./96						
							TAXABLE PARTY OF THE PARTY OF T	
Ī			CUNTRA	CTORS LICE	NSE			
IGNATURE			SEE	EVERSE SIDE FOR		DITIONS		
					TELEPHONE		DATE	
ITLE		FEIN	1			ADDE	SEAC OLLANOTO:	TO DE NOTES AS ONE



MODER

RFQ COPY

TYPE NAME/ADDRESS HERE

State of West Virginia Department of Administration Purchasing Division 2019 Washington Street East Post Office Box 50130 Charleston, WV 25305-0130

Request for Quotation

SMC00268

ADDRESS CORRESPONDENCE TO ATTENTION OF

ADDRESS CHANGES TO BE NOTED ABOVE

JOHN ABBOTT

304-558-2544

DIVISION OF CORRECTIONS ST. MARYS CORRECTIONAL CENTER

2880 N PLEASANTS HWY ST. MARYS, WV 26170 304-684-5500

F.O.B. FREIGHT TERMS TERMS OF SALE SHIP VIA DATE PRINTED 01/13/2009 BID OPENING DATE: BID OPENING TIME 01:30PM 02/12/2009 UNIT PRICE UOP ITEM NUMBER AMOUNT LINE QUANTITY WEST VIRGINIA STATE CODE 21-11-2 REQUIRES THAT ALL PERSONS DESIRING TO PERFORM CONTRACTING WORK IN THIS THE WEST VIRGINIA CONTRACTORS STATE MUST BE LICENSED. LICENSING BOARD IS EMPOWERED TO ISSUE THE CONTRACTORS APPLICATIONS FOR A CONTRACTORS LICENSE MAY BE MADE BY CONTACTING THE WEST VIRGINIA DIVISION OF LABOR CAPITOL COMPLEX, BUILDING 3, ROOM 319, CHARLESTON, WV TELEPHONE: (304) 558-7890. WEST VIRGINIA STATE CODE 21-11-11 REQUIRES ANY PROSPECTIVE BIDDER TO INCLUDE THE CONTRACTORS LICENSE NUMBER ON THEIR BID. BIDDER TO COMPLETE: CONTRACTORS NAME: CONTRACTORS LICENSE NO.: THE SUCCESSFUL BIDDER WILL BE REQUIRED TO FURNISH A COPY OF THEIR CONTRACTORS LICENSE PRIOR TO ISSUANCE OF A PURCHASE ORDER/CONTRACT APPLICABLE LAW THE WEST VIRGINIA STATE CODE, PURCHASING DIVISION RULES AND THE INFORMATION PROVIDED IN AND REGULATIONS, THE "REQUEST FOR QUOTATION" ISSUED BY THE PURCHASING DIVISION IS THE SOLE AUTHORITY GOVERNING THIS PROCUREMENT. ANY INFORMATION PROVIDED IN SPECIFICATION MANUALS, OR ANY OTHER SOURCE, VERBAL OR WRITTEN, WHICH CONTRADICTS OR ALTERS THE INFORMATION PROVIDED FROM THE SOURCES AS DESCRIBED IN THE ABOVE PARAGRAPH IS VOID AND OF NO EFFECT. SEE REVERSE SIDE FOR TERMS AND CONDITIONS TELEPHONE SIGNATURE TITLE



ENDOR

State of West Virginia
Department of Administration
Purchasing Division
2019 Washington Street East
Post Office Box 50130
Charleston, WV 25305-0130

Request for Quotation

SMC00268

÷	्रि	Þβ	G	E	ं	Ċ	}	
					3			

ADDRESS CORRESP	ONDENCE TO ATTENTION OF:
JOHN ABBOTT	
306-559-2566	

SH P T

RFQ COPY TYPE NAME/ADDRESS HERE

DIV:	ISION	0F	CORR	ECTI	ONS	•
ST.	MARYS	CC	RREC	TION	ΔL	CENTER

2880 N PLEASANTS HWY ST. MARYS, WV 26170 304-684-5500

DATE PRINTED TERMS OF SALE SHIP VIA F.O.B. FREIGHTTERMS 01/13/2009 BID OPENING DATE: 02/12/2009 BID OPENING TIME 01:30PM CAT. LINE QUANTITY UOP ITEM NUMBER UNIT PRICE AMOUNT BANKRUPTCY: | IN THE EVENT THE VENDOR/CONTRACTOR FILES FOR BANKRUPTICY PRIOTECTION, THIS CONTRAICT IS AUTOMATI-CALLY NULL AND VOID, AND IS TERMINATED WITHOUT FURTHER ORDER. REV. 1/2005 NOTICE A SIGNED BID MUST BE SUBMITTED TO: DEPARTMENT OF ADMINISTRATION PURCHASING DIVISION BUILDING 15 2019 WASHINGTON STREET, EAST CHARLES TON, WV 25305-0130 THE BID SHOULD CONTAIN THIS INFORMATION ON THE FACE OF THE ENVELOPE OR THE BID MAY NOT BE CONSIDERED: SEALED BID BUYER: JOHN ABBOTT----REQ. NO.: SMC00268-----BID OPENING DATE: 02/12/2009----BID OPENING TIME: 1:30 PM-----PLEASE PROVIDE A FAX NUMBER IN CASE IT IS NECESSARY TO CONTACT YOU REGARDING YOUR BID:

SEE REVERSE SIDE FOR TERMS AND CONDITIONS

SIGNATURE

TITLE

FEIN

ADDRESS CHANGES TO BE NOTED ABOVE



MODZMK

RFQ COPY

TYPE NAME/ADDRESS HERE

State of West Virginia
Department of Administration Purchasing Division 2019 Washington Street East Post Office Box 50130 Charleston, WV 25305-0130

Request for Quotation

SMC00268

2000	P/	١GE	32.	:
			_	

ADDRESS CORRESPONDENCE TO ATTENTION OF:

J	0	Н	N		A	В	В	0	T	T	
3	Ω	4	_	5	5	ន	_	2	5	4	

DIVISION OF CORRECTIONS ST. MARYS CORRECTIONAL CENTER

2880 N PLEASANTS HWY ST. MARYS, WV 26170 304-684-5500

DATE PRINTED	TERMS OF SALE	SHIP.	VIA	F.O.B	FREIGHT TERMS
01/13/2009					
BID OPENING DATE:	02/12/2009	ereningstered processes accommons accommon	BID	OPENING TIME (11:30PM
LINE QUAN	NTITY UOP	CAT. ITEM NU	MBER	UNIT PRICE	AMOUNT
		 			
		. [
PLEASE	PRINT OR T	PE NAME OF PE	RSON TO	CONTACT	
	NING THIS QU				
****	THIS IS T	E END OF RFQ	SMCOO	268 ***** TOTAL	
		-	Ì		
			ļ		
			-		
				•	
					ļ
			·		
***************************************	[
ĺ					
L	3	SEE REVERSE SIDE FOR TE		PITIONS	
SIGNATURE			TELEPHONE	DATE	
TITLE	FEIN			ADDRESS CHANGE	S TO BE NOTED ABOVE

SECTION 03300 - CAST-IN-PLACE CONCRETE

PART 1 - GENERAL

1.1 SUMMARY

A. This Section specifies cast-in place concrete, including formwork, reinforcement, concrete materials, mix design, placement procedures, and finishes.

1.2 DEFINITIONS

A. Cementitious Materials: Portland cement alone or in combination with one or more of blended hydraulic cement, fly ash and other pozzolans, ground granulated blast-furnace slag.

1.3 SUBMITTALS

- A. Product Data: For each type of manufactured material and product indicated.
- B. Design Mixes: For each concrete mix. Include alternate mix designs when characteristics of materials, project conditions, weather, test results, or other circumstances warrant adjustments.
 - 1. Indicate amounts of mix water to be withheld for later addition at Project site.
- C. Steel Reinforcement Shop Drawings: Details of fabrication, bending, and placement, prepared according to ACI 315, "Details and Detailing of Concrete Reinforcement." Include material, grade, bar schedules, stirrup spacing, bent bar diagrams, arrangement, and supports of concrete reinforcement. Include special reinforcement required for openings through concrete structures.
- D. Material Certificates: Signed by manufacturers certifying that each of the following items complies with requirements:
 - 1. Cementitious materials and aggregates.
 - 2. Form materials and form-release agents.
 - 3. Steel reinforcement and reinforcement accessories.
 - 4. Admixtures.
 - 5. Curing materials.
 - Floor and slab treatments.
 - 7. Bonding agents.
 - 8. Adhesives.
 - 9. Vapor retarders.
 - 10. Epoxy joint filler.
 - 11. Joint-filler strips.
- E. Minutes of preinstallation conference.

1.4 QUALITY ASSURANCE

- A. Installer Qualifications: An experienced installer who has completed concrete Work similar in material, design, and extent to that indicated for this Project and whose work has resulted in construction with a record of successful in-service performance.
- B. Manufacturer Qualifications: A firm experienced in manufacturing ready-mixed concrete products complying with ASTM C 94 requirements for production facilities and equipment.
 - Manufacturer must be certified according to the National Ready Mixed Concrete Association's Certification of Ready Mixed Concrete Production Facilities.
- C. Testing Agency Qualifications: An independent testing agency, acceptable to authorities having jurisdiction, qualified according to ASTM C 1077 and ASTM E 329 to conduct the testing indicated, as documented according to ASTM E 548.
 - 1. Personnel conducting field tests shall be qualified as ACI Concrete Field Testing Technician, Grade 1, according to ACI CP-1 or an equivalent certification program.
- D. Source Limitations: Obtain each type or class of cementitious material of the same brand from the same manufacturer's plant, each aggregate from one source, and each admixture from the same manufacturer.
- E. ACI Publications: Comply with the following, unless more stringent provisions are indicated:
 - 1. ACI 301, "Specification for Structural Concrete."
 - 2. ACI 117, "Specifications for Tolerances for Concrete Construction and Materials."
- F. Preinstallation Conference: Conduct conference at Project site to comply with requirements in Division 1 Section "Project Meetings."
 - 1. Before submitting design mixes, review concrete mix design and examine procedures for ensuring quality of concrete materials. Require representatives of each entity directly concerned with cast-in-place concrete to attend, including the following:
 - a. Contractor's superintendent.
 - b. Independent testing agency responsible for concrete design mixes.
 - c. Ready-mix concrete producer.
 - d. Concrete subcontractor.

1.5 DELIVERY, STORAGE, AND HANDLING

A. Deliver, store, and handle steel reinforcement to prevent bending and damage.

PART 2 - PRODUCTS

2.1 FORM-FACING MATERIALS

- A. Smooth-Formed Finished Concrete: Form-facing panels that will provide continuous, true, and smooth concrete surfaces. Furnish in largest practicable sizes to minimize number of joints.
 - 1. Exterior-grade plywood panels, suitable for concrete forms, complying with DOC PS 1, and as follows:
 - a. B-B (Concrete Form), Class 1, or better, mill oiled and edge sealed.

- B. Rough-Formed Finished Concrete: Plywood, lumber, metal, or another approved material. Provide lumber dressed on at least two edges and one side for tight fit.
- C. Chamfer Strips: Wood, metal, PVC, or rubber strips, 3/4 by 3/4 inch (19 by 19 mm), minimum.
- D. Form-Release Agent: Commercially formulated form-release agent that will not bond with, stain, or adversely affect concrete surfaces and will not impair subsequent treatments of concrete surfaces.
 - 1. Formulate form-release agent with rust inhibitor for steel form-facing materials.
- E. Form Ties: Factory-fabricated, removable or snap-off metal or glass-fiber-reinforced plastic form ties designed to resist lateral pressure of fresh concrete on forms and to prevent spalling of concrete on removal.
 - 1. Furnish units that will leave no corrodible metal closer than 1 inch (25 mm) to the plane of the exposed concrete surface.

2.2 STEEL REINFORCEMENT

- A. Reinforcing Bars: ASTM A 615/A 615M, Grade 60 (Grade 420), deformed.
- B. Deformed-Steel Welded Wire Fabric: ASTM A 497, flat sheet.
- C. Welded Wire Fabric: ASTM A 185, welded steel wire fabric.

2.3 REINFORCEMENT ACCESSORIES

- A. Bar Supports: Bolsters, chairs, spacers, and other devices for spacing, supporting, and fastening reinforcing bars and welded wire fabric in place. Manufacture bar supports according to CRSI's "Manual of Standard Practice" from steel wire, plastic, or precast concrete or fiber-reinforced concrete of greater compressive strength than concrete, and as follows:
 - 1. For concrete surfaces exposed to view where legs of wire bar supports contact forms, use CRSI Class 1 plastic-protected or CRSI Class 2 stainless-steel bar supports.
- B. Joint Dowel Bars: Plain-steel bars, ASTM A 615/A 615M, Grade 60 (Grade 420). Cut bars true to length with ends square and free of burrs.

2.4 CONCRETE MATERIALS

- A. Portland Cement: ASTM C 150, Type I.
 - 1. Fly Ash: ASTM C 618, Class C or F.
- B. Normal-Weight Aggregate: ASTM C 33, uniformly graded.
- C. Water: Potable and complying with ASTM C 94.

2.5 ADMIXTURES

- A. General: Admixtures certified by manufacturer to contain not more than 0.1 percent water-soluble chloride ions by mass of cementitious material and to be compatible with other admixtures and cementitious materials. Do not use admixtures containing calcium chloride.
- B. Air-Entraining Admixture: ASTM C 260.
- C. Other Admixtures: Other Admixtures may be proposed by the Contractor as part of the mix design submittal. Other admixtures submitted as part of the design process shall include product data and material certificates.

2.6 VAPOR RETARDERS

- A. Vapor Retarder: ASTM E 1745, Class B, five-ply, nylon- or polyester-cord-reinforced, high-density polyethylene sheet; 10 mils (0.25 mm) thick.
 - 1. Available Product: Subject to compliance with requirements, a product that may be incorporated into the Work includes, but is not limited to, "Griffolyn T-85" by Reef Industries Inc; Stego Wrap by Sego Industries LLC; Dura-skrim D16 WB by Raven Industries.
 - Accessories: Seam tape: High Density Polyethylene Tape with pressure sensitive adhesive.
 Minimum width 4 inches. Pipe boots: constructed from vapor barier material and pressure sensitive tape.

2.7 CURING MATERIALS

- A. Moisture-Retaining Cover: ASTM C 171, white burlap-polyethylene sheet.
- B. Water: Potable.
- C. Liquid Membrane-Forming Curing Compound: Liquid-type membrane-forming curing compound complying with ASTM C 309, Type I, Class A Moisture loss not more than 0.055 gr./sq. cm. when applied at 200 sq. ft./gal.

2.8 RELATED MATERIALS

- A. Joint-Filler Strips: ASTM D 1751, asphalt-saturated cellulosic fiber.
- B. Bonding Agent: ASTM C 1059, Type II, non-redispersible, acrylic emulsion or styrene butadiene.

2.9 CONCRETE MIXES

- A. Prepare design mixes for each type and strength of concrete listed on the structural drawings determined by either laboratory trial mix or field test data bases, as follows:
 - Proportion normal-weight concrete according to ACI 211.1 and ACI 301.
- B. Use a qualified independent testing agency for preparing and reporting proposed mix designs for the laboratory trial mix basis.
- C. Cementitious Materials: Limit percentage, by weight, of cementitious materials other than portland cement in concrete as follows:

- 1. Fly Ash: 20 percent.
- D. Maximum Water-Cementitious Materials Ratio: Concrete requirements see structural drawings.
- E. Air Content: Add air-entraining admixture at manufacturer's prescribed rate to result in concrete at point of placement having an air content as indicated on the structural drawings.
- F. Admixtures: Use admixtures according to manufacturer's written instructions and as approved in the design mixes submitted and stamped approved.

2.10 FABRICATING REINFORCEMENT

A. Fabricate steel reinforcement according to CRSI's "Manual of Standard Practice."

2.11 CONCRETE MIXING

- A. Ready-Mixed Concrete: Measure, batch, mix, and deliver concrete according to ASTM C 94, and furnish batch ticket information.
 - 1. When air temperature is between 85 and 90 deg F (30 and 32 deg C), reduce mixing and delivery time from 1-1/2 hours to 75 minutes; when air temperature is above 90 deg F (32 deg C), reduce mixing and delivery time to 60 minutes.

2.12 REPAIR MATERIALS

A. Repair Underlayment: Referred to as "leveling compound" on the drawings. "Durathin" by L&M Chemicals, Inc.

PART 3 - EXECUTION

3.1 FORMWORK

- A. Design, erect, shore, brace, and maintain formwork, according to ACI 301, to support vertical, lateral, static, and dynamic loads, and construction loads that might be applied, until concrete structure can support such loads.
- B. Construct formwork so concrete members and structures are of size, shape, alignment, elevation, and position indicated, within tolerance limits of ACI 117.
- C. Limit concrete surface irregularities, designated by ACI 347R as abrupt or gradual, as follows:
 - 1. Class A, 1/8 inch (3 mm).
- D. Construct forms tight enough to prevent loss of concrete mortar.
- E. Fabricate forms for easy removal without hammering or prying against concrete surfaces. Provide crush or wrecking plates where stripping may damage cast concrete surfaces. Provide top forms for inclined surfaces steeper than 1.5 horizontal to 1 vertical. Kerf wood inserts for forming keyways, reglets, recesses, and the like, for easy removal.

- Do not use rust-stained steel form-facing material.
- F. Set edge forms, bulkheads, and intermediate screed strips for slabs to achieve required elevations and slopes in finished concrete surfaces. Provide and secure units to support screed strips; use strike-off templates or compacting-type screeds.
- G. Provide temporary openings for cleanouts and inspection ports where interior area of formwork is inaccessible. Close openings with panels tightly fitted to forms and securely braced to prevent loss of concrete mortar. Locate temporary openings in forms at inconspicuous locations.
- H. Chamfer exterior corners and edges of permanently exposed concrete.
- Form openings, chases, offsets, sinkages, keyways, reglets, blocking, screeds, and bulkheads required in the Work. Determine sizes and locations from trades providing such items.
- J. Clean forms and adjacent surfaces to receive concrete. Remove chips, wood, sawdust, dirt, and other debris just before placing concrete.
- K. Retighten forms and bracing before placing concrete, as required, to prevent mortar leaks and maintain proper alignment.
- L. Coat contact surfaces of forms with form-release agent, according to manufacturer's written instructions, before placing reinforcement.

3.2 EMBEDDED ITEMS

- A. Place and secure anchorage devices and other embedded items required for adjoining work that is attached to or supported by cast-in-place concrete. Use Setting Drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
 - Install anchor bolts, accurately located, to elevations required.

3.3 REMOVING AND REUSING FORMS

- A. General: Formwork, for sides of beams, walls, columns, and similar parts of the Work, that does not support weight of concrete may be removed after cumulatively curing at not less than 50 deg F (10 deg C) for 24 hours after placing concrete provided concrete is hard enough to not be damaged by form-removal operations and provided curing and protection operations are maintained.
- B. Leave formwork, for beam soffits, joists, slabs, and other structural elements, that supports weight of concrete in place until concrete has achieved the following:
 - 1. At least 70 percent of 28-day design compressive strength.
 - 2. Determine compressive strength of in-place concrete by testing representative field- or laboratory-cured test specimens according to ACI 301.
 - 3. Remove forms only if shores have been arranged to permit removal of forms without loosening or disturbing shores.
- C. Clean and repair surfaces of forms to be reused in the Work. Split, frayed, delaminated, or otherwise damaged form-facing material will not be acceptable for exposed surfaces. Apply new form-release agent.

D. When forms are reused, clean surfaces, remove fins and laitance, and tighten to close joints. Align and secure joints to avoid offsets. Do not use patched forms for exposed concrete surfaces unless approved by Architect.

3.4 VAPOR RETARDERS

A. Vapor Retarder: Place, protect, and repair vapor-retarder sheets according to ASTM E 1643 and manufacturer's written instructions.

3.5 STEEL REINFORCEMENT

- A. General: Comply with CRSI's "Manual of Standard Practice" for placing reinforcement.
 - 1. Do not cut or puncture vapor retarder. Repair damage and reseal vapor retarder before placing concrete.
- B. Clean reinforcement of loose rust and mill scale, earth, ice, and other foreign materials.
- C. Accurately position, support, and secure reinforcement against displacement. Locate and support reinforcement with bar supports to maintain minimum concrete cover. Do not tack weld crossing reinforcing bars.
- D. Set wire ties with ends directed into concrete, not toward exposed concrete surfaces.
- E. Install welded wire fabric in longest practicable lengths on bar supports spaced to minimize sagging. Lap edges and ends of adjoining sheets at least one mesh spacing. Offset laps of adjoining sheet widths to prevent continuous laps in either direction. Lace overlaps with wire.

3.6 JOINTS

- A. General: Construct joints true to line with faces perpendicular to surface plane of concrete.
- B. Construction Joints: Install so strength and appearance of concrete are not impaired, at locations indicated or as approved by Architect.
 - 1. Place joints perpendicular to main reinforcement. Continue reinforcement across construction joints, unless otherwise indicated. Do not continue reinforcement through sides of strip placements of floors and slabs.
 - 2. Form from preformed galvanized steel, plastic keyway-section forms, or bulkhead forms with keys, unless otherwise indicated. Embed keys at least 1-1/2 inches (38 mm) into concrete.
 - 3. Use a bonding agent at locations where fresh concrete is placed against hardened or partially hardened concrete surfaces.
- C. Contraction Joints in Slabs-on-Grade: Form weakened-plane contraction joints, sectioning concrete into areas as indicated. Construct contraction joints for a depth equal to at least one-fourth of concrete thickness, as follows:
 - 1. Sawed Joints: Form contraction joints with power saws equipped with shatterproof abrasive or diamond-rimmed blades. Cut 1/8-inch- (3-mm-) wide joints into concrete when cutting action will not tear, abrade, or otherwise damage surface and before concrete develops random contraction cracks.

- D. Isolation Joints in Slabs-on-Grade: After removing formwork, install joint-filler strips at slab junctions with vertical surfaces, such as column pedestals, foundation walls, grade beams, and other locations, as indicated.
 - 1. Extend joint-filler strips full width and depth of joint, terminating flush with finished concrete surface, unless otherwise indicated.
 - 2. Terminate full-width joint-filler strips not less than 1/2 inch (12 mm) or more than 1 inch (25 mm) below finished concrete surface where joint sealants, specified in Division 7 Section "Joint Sealants," are indicated.
 - 3. Install joint-filler strips in lengths as long as practicable. Where more than one length is required, lace or clip sections together.
- E. Dowel Joints: Install dowel sleeves and dowels or dowel bar and support assemblies at joints where indicated.
 - 1. Use dowel sleeves to prevent concrete bonding to one side of joint.

3.7 CONCRETE PLACEMENT

- A. Before placing concrete, verify that installation of formwork, reinforcement, and embedded items is complete and that required inspections have been performed.
- B. Before placing concrete, water may be added at Project site, subject to limitations of ACI 301.
- C. Deposit concrete continuously or in layers of such thickness that no new concrete will be placed on concrete that has hardened enough to cause seams or planes of weakness. If a section cannot be placed continuously, provide construction joints as specified. Deposit concrete to avoid segregation.
- D. Deposit concrete in forms in horizontal layers no deeper than 24 inches (600 mm) and in a manner to avoid inclined construction joints. Place each layer while preceding layer is still plastic, to avoid cold joints.
 - Consolidate placed concrete with mechanical vibrating equipment. Use equipment and procedures for consolidating concrete recommended by ACI 309R.
 - 2. Do not use vibrators to transport concrete inside forms. Insert and withdraw vibrators vertically at uniformly spaced locations no farther than the visible effectiveness of the vibrator. Place vibrators to rapidly penetrate placed layer and at least 6 inches (150 mm) into preceding layer. Do not insert vibrators into lower layers of concrete that have begun to lose plasticity. At each insertion, limit duration of vibration to time necessary to consolidate concrete and complete embedment of reinforcement and other embedded items without causing mix constituents to segregate.
- E. Deposit and consolidate concrete for floors and slabs in a continuous operation, within limits of construction joints, until placement of a panel or section is complete.
 - 1. Consolidate concrete during placement operations so concrete is thoroughly worked around reinforcement and other embedded items and into corners.
 - 2. Maintain reinforcement in position on chairs during concrete placement.
 - Screed slab surfaces with a straightedge and strike off to correct elevations.
 - 4. Slope surfaces uniformly to drains where required.
 - 5. Begin initial floating using bull floats or darbies to form a uniform and open-textured surface plane, free of humps or hollows, before excess moisture or bleedwater appears on the surface. Do not further disturb slab surfaces before starting finishing operations.

- F. Cold-Weather Placement: Comply with ACI 306.1 and as follows. Protect concrete work from physical damage or reduced strength that could be caused by frost, freezing actions, or low temperatures.
 - 1. When air temperature has fallen to or is expected to fall below 40 deg F (4.4 deg C), uniformly heat water and aggregates before mixing to obtain a concrete mixture temperature of not less than 50 deg F (10 deg C) and not more than 80 deg F (27 deg C) at point of placement.

2. Do not use frozen materials or materials containing ice or snow. Do not place concrete on frozen subgrade or on subgrade containing frozen materials.

3. Do not use calcium chloride, salt, or other materials containing antifreeze agents or chemical accelerators, unless otherwise specified and approved in mix designs.

- G. Hot-Weather Placement: Place concrete according to recommendations in ACI 305R and as follows, when hot-weather conditions exist:
 - 1. Cool ingredients before mixing to maintain concrete temperature below 90 deg F (32 deg C) at time of placement. Chilled mixing water or chopped ice may be used to control temperature, provided water equivalent of ice is calculated to total amount of mixing water. Using liquid nitrogen to cool concrete is Contractor's option.

2. Cover steel reinforcement with water-soaked burlap so steel temperature will not exceed ambient

air temperature immediately before embedding in concrete.

3. Fog-spray forms, steel reinforcement, and subgrade just before placing concrete. Keep subgrade moisture uniform without standing water, soft spots, or dry areas.

3.8 FINISHING FORMED SURFACES

- A. Smooth-Formed Finish: As-cast concrete texture imparted by form-facing material, arranged in an orderly and symmetrical manner with a minimum of seams. Repair and patch tie holes and defective areas. Remove fins and other projections exceeding 1/8 inch (3 mm) in height.
 - 1. Apply to concrete surfaces exposed to public view or to be covered with a coating or covering material applied directly to concrete, such as waterproofing, dampproofing, veneer plaster, or painting.

2. Do not apply rubbed finish to smooth-formed finish.

- B. Related Unformed Surfaces: At tops of walls, horizontal offsets, and similar unformed surfaces adjacent to formed surfaces, strike off smooth and finish with a texture matching adjacent formed surfaces. Continue final surface treatment of formed surfaces uniformly across adjacent unformed surfaces, unless otherwise indicated.
- C. Rubbed Finish: Not later than one day after form removal, moisten concrete surfaces and rub with carborundum brick or another abrasive until producing a uniform color and texture. Do not apply cement grout other than that created by the rubbing process.

3.9 FINISHING FLOORS AND SLABS

- A. General: Comply with recommendations in ACI 302.1R for screeding, restraightening, and finishing operations for concrete surfaces. Do not wet concrete surfaces.
- B. Scratch Finish: While still plastic, texture concrete surface that has been screeded and bull-floated or darbied. Use stiff brushes, brooms, or rakes.

- 1. Apply scratch finish to surfaces indicated and to surfaces to receive concrete floor topping or mortar setting beds for ceramic or quarry tile, portland cement terrazzo, and other bonded cementitious floor finishes.
- C. Float Finish: Consolidate surface with power-driven floats or by hand floating if area is small or inaccessible to power driven floats. Restraighten, cut down high spots, and fill low spots. Repeat float passes and restraightening until surface is left with a uniform, smooth, granular texture.
 - 1. Apply float finish to surfaces indicated, to surfaces to receive trowel finish, and to floor and slab surfaces to be covered with fluid-applied or sheet waterproofing, built-up or membrane roofing, or sand-bed terrazzo.
- D. Trowel Finish: After applying float finish, apply first trowel finish and consolidate concrete by hand or power-driven trowel. Continue troweling passes and restraighten until surface is free of trowel marks and uniform in texture and appearance. Grind smooth any surface defects that would telegraph through applied coatings or floor coverings.
 - 1. Apply a trowel finish to surfaces indicated and to floor and slab surfaces exposed to view or to be covered with resilient flooring, carpet, ceramic or quarry tile set over a cleavage membrane, paint, or another thin film-finish coating system
 - 2. Finish and measure surface so gap at any point between concrete surface and an unleveled freestanding 10-foot- (3.05-m-) long straightedge, resting on two high spots and placed anywhere on the surface, does not exceed the following:
 - a. 1/8 inch (3.2 mm).
- E. Trowel and Fine-Broom Finish: Apply a partial trowel finish, stopping after second troweling, to surfaces indicated and to surfaces where ceramic or quarry tile is to be installed by either thickset or thin-set method. Immediately after second troweling, and when concrete is still plastic, slightly scarify surface with a fine broom.
- F. Broom Finish: Apply a broom finish to exterior concrete platforms, steps, and ramps, and elsewhere as indicated.
 - Immediately after float finishing, slightly roughen trafficked surface by brooming with fiberbristle broom perpendicular to main traffic route. Coordinate required final finish with Architect before application.

3.10 MISCELLANEOUS CONCRETE ITEMS

- A. Filling In: Fill in holes and openings left in concrete structures, unless otherwise indicated, after work of other trades is in place. Mix, place, and cure concrete, as specified, to blend with in-place construction. Provide other miscellaneous concrete filling indicated or required to complete Work.
- B. Curbs: Provide monolithic finish to interior curbs by stripping forms while concrete is still green and by steel-troweling surfaces to a hard, dense finish with corners, intersections, and terminations slightly rounded.
- C. Equipment Bases and Foundations: Provide machine and equipment bases and foundations as shown on Drawings. Set anchor bolts for machines and equipment at correct elevations, complying with diagrams or templates of manufacturer furnishing machines and equipment.

3.11 CONCRETE PROTECTION AND CURING

- A. General: Protect freshly placed concrete from premature drying and excessive cold or hot temperatures. Comply with ACI 306.1 for cold-weather protection and with recommendations in ACI 305R for hotweather protection during curing.
- B. Evaporation Retarder: Apply evaporation retarder to unformed concrete surfaces if hot, dry, or windy conditions cause moisture loss approaching 0.2 lb/sq. ft. x h (1 kg/sq. m x h) before and during finishing operations. Apply according to manufacturer's written instructions after placing, screeding, and bull floating or darbying concrete, but before float finishing.
- C. Formed Surfaces: Cure formed concrete surfaces, including underside of beams, supported slabs, and other similar surfaces. If forms remain during curing period, moist cure after loosening forms. If removing forms before end of curing period, continue curing by one or a combination of the following methods:
- D. Unformed Surfaces: Begin curing immediately after finishing concrete. Cure unformed surfaces, including floors and slabs, concrete floor toppings, and other surfaces, by one or a combination of the following methods:
 - Moisture-Retaining-Cover Curing: Cover concrete surfaces with moisture-retaining cover for curing concrete, placed in widest practicable width, with sides and ends lapped at least 12 inches (300 mm), and sealed by waterproof tape or adhesive. Cure for not less than seven days. Immediately repair any holes or tears during curing period using cover material and waterproof tape.
 - a. Cure concrete surfaces to receive floor coverings with either a moisture-retaining cover or a curing compound that the manufacturer recommends for use with floor coverings.

3.12 JOINT FILLING

- A. Prepare, clean, and install joint filler according to manufacturer's written instructions.
 - 1. Defer joint filling until concrete has aged at least six months. Do not fill joints until construction traffic has permanently ceased.
- B. Remove dirt, debris, saw cuttings, curing compounds, and sealers from joints; leave contact faces of joint clean and dry.
- C. Install semirigid epoxy joint filler full depth in saw-cut joints and at least 2 inches (50 mm) deep in formed joints. Overfill joint and trim joint filler flush with top of joint after hardening.

3.13 CONCRETE SURFACE REPAIRS

- A. Defective Concrete: Repair and patch defective areas when approved by Architect. Remove and replace concrete that cannot be repaired and patched to Architect's approval.
- B. Patching Mortar: Mix dry-pack patching mortar, consisting of one part portland cement to two and one-half parts fine aggregate passing a No. 16 (1.2-mm) sieve, using only enough water for handling and placing.

- C. Repairing Formed Surfaces: Surface defects include color and texture irregularities, cracks, spalls, air bubbles, honeycombs, rock pockets, fins and other projections on the surface, and stains and other discolorations that cannot be removed by cleaning.
 - 1. Immediately after form removal, cut out honeycombs, rock pockets, and voids more than 1/2 inch (13 mm) in any dimension in solid concrete but not less than 1 inch (25 mm) in depth. Make edges of cuts perpendicular to concrete surface. Clean, dampen with water, and brush-coat holes and voids with bonding agent. Fill and compact with patching mortar before bonding agent has dried. Fill form-tie voids with patching mortar or cone plugs secured in place with bonding agent.
 - 2. Repair defects on surfaces exposed to view by blending white portland cement and standard portland cement so that, when dry, patching mortar will match surrounding color. Patch a test area at inconspicuous locations to verify mixture and color match before proceeding with patching. Compact mortar in place and strike off slightly higher than surrounding surface.
 - 3. Repair defects on concealed formed surfaces that affect concrete's durability and structural performance as determined by Architect.
- D. Repairing Unformed Surfaces: Test unformed surfaces, such as floors and slabs, for finish and verify surface tolerances specified for each surface. Correct low and high areas. Test surfaces sloped to drain for trueness of slope and smoothness; use a sloped template.
 - 1. Repair finished surfaces containing defects. Surface defects include spalls, popouts, honeycombs, rock pockets, crazing and cracks in excess of 0.01 inch (0.25 mm) wide or that penetrate to reinforcement or completely through unreinforced sections regardless of width, and other objectionable conditions.
 - 2. After concrete has cured at least 14 days, correct high areas by grinding.
 - 3. Correct localized low areas during or immediately after completing surface finishing operations by cutting out low areas and replacing with patching mortar. Finish repaired areas to blend into adjacent concrete.
 - 4. Repair defective areas, except random cracks and single holes 1 inch (25 mm) or less in diameter, by cutting out and replacing with fresh concrete. Remove defective areas with clean, square cuts and expose steel reinforcement with at least 3/4 inch (19 mm) clearance all around. Dampen concrete surfaces in contact with patching concrete and apply bonding agent. Mix patching concrete of same materials and mix as original concrete except without coarse aggregate. Place, compact, and finish to blend with adjacent finished concrete. Cure in same manner as adjacent concrete.
 - 5. Repair random cracks and single holes 1 inch (25 mm) or less in diameter with patching mortar. Groove top of cracks and cut out holes to sound concrete and clean off dust, dirt, and loose particles. Dampen cleaned concrete surfaces and apply bonding agent. Place patching mortar before bonding agent has dried. Compact patching mortar and finish to match adjacent concrete. Keep patched area continuously moist for at least 72 hours.
- E. Perform structural repairs of concrete, subject to Architect's approval, using epoxy adhesive and patching mortar.
- F. Repair materials and installation not specified above may be used, subject to Architect's approval.

3.14 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified independent testing and inspecting agency to sample materials, perform tests, and submit test reports during concrete placement according to requirements specified in this Article.
- B. Testing Services: Testing of composite samples of fresh concrete obtained according to ASTM C 172 shall be performed according to the following requirements:


- 1. Testing Frequency: Obtain one composite sample for each day's pour of each concrete mix exceeding 5 cu. yd. (4 cu. m), but less than 25 cu. yd. (19 cu. m), plus one set for each additional 50 cu. yd. (38 cu. m) or fraction thereof.
- 2. Slump: ASTM C 143; one test at point of placement for each composite sample, but not less than one test for each day's pour of each concrete mix. Perform additional tests when concrete consistency appears to change.

3. Air Content: ASTM C 231, pressure method, for normal-weight concrete; ASTM C 173, one test for each composite sample, but not less than one test for each day's pour of each concrete mix.

- 4. Concrete Temperature: ASTM C 1064; one test hourly when air temperature is 40 deg F (4.4 deg C) and below and when 80 deg F (27 deg C) and above, and one test for each composite sample.
- 5. Compressive-Strength Tests: ASTM C 39; test two laboratory-cured specimens at 7 days and two at 28 days.
 - a. A compressive-strength test shall be the average compressive strength from two specimens obtained from same composite sample and tested at age indicated.
- C. Strength of each concrete mix will be satisfactory if every average of any three consecutive compressive-strength tests equals or exceeds specified compressive strength and no compressive-strength test value falls below specified compressive strength by more than 500 psi (3.4 MPa).
- D. Test results shall be reported in writing to Architect, Structural Engineer, concrete manufacturer, and Contractor within 48 hours of testing. Reports of compressive-strength tests shall contain Project identification name and number, date of concrete placement, name of concrete testing and inspecting agency, location of concrete batch in Work, design compressive strength at 28 days, concrete mix proportions and materials, compressive breaking strength, and type of break for both 7-and 28-day tests.
- E. Nondestructive Testing: Impact hammer, sonoscope, or other nondestructive device may be permitted by Architect but will not be used as sole basis for approval or rejection of concrete.
- F. Additional Tests: Testing and inspecting agency shall make additional tests of concrete when test results indicate that slump, air entrainment, compressive strengths, or other requirements have not been met, as directed by Architect. Testing and inspecting agency may conduct tests to determine adequacy of concrete by cored cylinders complying with ASTM C 42 or by other methods as directed by Architect.

END OF SECTION 03300

38



G-46 REV. 5-7	_	ENGINEERING	COMPUTATION SHEET	25	SHEET NO.
TITLE OF PIR	OU OR STUDY	MARYS_		PROJ. OR STUDY NO.	
SUBJECT	FUEL STO	RAGE		Works	
+	PLAN VIEL	COMPUTER	DA1	TE	
9 1 2	2 3 4 5 6 7	COMPUTER 8 9 10 11 12 13 14	15 16 17 18 19 20 21	22 23 24 25	19 <u>26 27 28 29 30</u>
1 .			ו בבמתווכי ו		
2	Marie Contraction of the Contrac	~ U	RT 420095MA Taringar f) tu	
3	X	-वास	K 430005MA	,7/1	\sim
4 .					
5					/ 5% \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \
6	and a second sec	WALL SO			
7	AND THE PROPERTY OF THE PROPER	_ 20	10 DE 1	THE RESERVE ASSESSMENT OF THE PARTY OF THE P	
			199.		
8			,		
9	F			/ ~	
10	(L) D (\ \ \	
11				Ţ	
12				! 	
13		- UT	/ "	<u>t</u>	
14					
	W Com				- 2,
16 N	W 6	+ P		0	24.0
17		it à		0	0
19 🔪	Z O ~	CRETE CRETE			
19	$H_{\mathfrak{D}}$			R	
20	ABOUG	۸۱ ک	Son Kores 11" lie Rea	रू ला	
21	16			164	
22	793	1) 27 7	200		
23	P	5. ∧	8	7	
24	Ŕ	+	CO 11"		
25	GRADU.		()		
26 .			X CO	, E	
27				162	
28		·			
29	A. Land				+//
30				and the second s	N ·
31	L. C. Commission of Park				10
.			To the second se		•
32		22'	10		
33	X				
بر بالاست. الاست.	No.				
35	B. T.	FINALL			
36	Q/AU DO	of wall warened			
37		2	3	-	

RFQ No.	SMC00268
VI 02 110.	

STATE OF WEST VIRGINIA Purchasing Division

PURCHASING AFFIDAVIT

VENDOR OWING A DEBT TO THE STATE:

West Virginia Code §5A-3-10a provides that: No contract or renewal of any contract may be awarded by the state or any of its political subdivisions to any vendor or prospective vendor when the vendor or prospective vendor or a related party to the vendor or prospective vendor is a debtor and the debt owed is an amount greater than one thousand dollars in the aggregate.

PUBLIC IMPROVEMENT CONTRACTS & DRUG-FREE WORKPLACE ACT:

If this is a solicitation for a public improvement construction contract, the vendor, by its signature below, affirms that it has a written plan for a drug-free workplace policy in compliance with Article 1D, Chapter 21 of the **West Virginia Code**. The vendor **must** make said affirmation with its bid submission. Further, public improvement construction contract may not be awarded to a vendor who does not have a written plan for a drug-free workplace policy in compliance with Article 1D, Chapter 21 of the **West Virginia Code** and who has not submitted that plan to the appropriate contracting authority in timely fashion. For a vendor who is a subcontractor, compliance with Section 5, Article 1D, Chapter 21 of the **West Virginia Code** may take place before their work on the public improvement is begun.

ANTITRUST:

In submitting a bid to any agency for the state of West Virginia, the bidder offers and agrees that if the bid is accepted the bidder will convey, sell, assign or transfer to the state of West Virginia all rights, title and interest in and to all causes of action it may now or hereafter acquire under the antitrust laws of the United States and the state of West Virginia for price fixing and/or unreasonable restraints of trade relating to the particular commodities or services purchased or acquired by the state of West Virginia. Such assignment shall be made and become effective at the time the purchasing agency tenders the initial payment to the bidder.

I certify that this bid is made without prior understanding, agreement, or connection with any corporation, firm, limited liability company, partnership or person or entity submitting a bid for the same materials, supplies, equipment or services and is in all respects fair and without collusion or fraud. I further certify that I am authorized to sign the certification on behalf of the bidder or this bid.

LICENSING:

Vendors must be licensed and in good standing in accordance with any and all state and local laws and requirements by any state or local agency of West Virginia, including, but not limited to, the West Virginia Secretary of State's Office, the West Virginia Tax Department, West Virginia Insurance Commission, or any other state agencies or political subdivision. Furthermore, the vendor must provide all necessary releases to obtain information to enable the Director or spending unit to verify that the vendor is licensed and in good standing with the above entities.

CONFIDENTIALITY:

The vendor agrees that he or she will not disclose to anyone, directly or indirectly, any such personally identifiable information or other confidential information gained from the agency, unless the individual who is the subject of the information consents to the disclosure in writing or the disclosure is made pursuant to the agency's policies, procedures and rules. Vendor further agrees to comply with the Confidentiality Policies and Information Security Accountability Requirements, set forth in http://www.state.wv.us/admin/purchase/privacy/noticeConfidentiality.pdf.

Under penalty of law for false swearing (**West Virginia Code** §61-5-3), it is hereby certified that the vendor affirms and acknowledges the information in this affidavit and is in compliance with the requirements as stated.

Vendor's Name:		
Authorized Signature:	Date:	
Purchasing Affidavit (Revised 01/01/09)		