

UPDATED QUANTITIES

PAVING QUANTITIES

LOCATION		LENGTH	ITEM ASPHALT 402001-001 TON	ITEM ASPHALT BASE 401001-001 TON	ITEM CLASS 1 307001-001 C.Y.	ITEM FABRIC SEPARATION 207034-000 S.Y.	ITEM FABRIC STABILIZATION 207033-000 S.Y.	ITEM CLASS 10 307005-000 TON	SUBGRADE PREP ITEM 228-01 SY	REMARKS
STATION	STATION									
ACCESS ROAD										
0+00.00	9+00.00	900.00'	212	1133	0	0	0	382	2643	
9+00.00	21+50.00	1250.00'	292	1555	1210	0	7292	1225	0	
21+50.00	33+24.24	1174.24'	248	1324	1030	0	5479	1043	0	
READINESS CENTER										
WESTERN PARKING AREA		N/A	503	1803	3832	11,496	0	N/A	N/A	
TOTAL		3324.24'	1721	7058	8006	17297	12771	2650	2643	

DELETED SUBGRADE ITEM AND ADDED FABRIC STABILIZATION ITEM

PIPE CULVERTS

LOCATION		SKEW	CORRUGATED METAL PIPE			STRUCTURES	REMARKS
STATION	STATION		18"	36"	48"		
0+00.00	0+54.07	55'					
0+00.00	2+60.17			261'			
0+00.00	2+62.66			263'			
0+00.00	4+51.03		452'			MODIFIED JUNCTION BOX AT STA. 3+93.00	

SIGNING QUANTITIES

SIGN NAME	SIGN NUMBER	SHEET NO.	WIDTH	HEIGHT	FLAT SHEET	EXTRUDED PANEL	U-CHANNEL		POST REMOVAL	REUSE EX. SPTS.
					0.080 SF		2.00 # / FT	3.00 # / FT		
STOP SIGN	R1-1	C200 & C201	30"	30"	31.25		62.5			
S CURVE	W1-5	C201	36"	36"	18.00		26.0			
SPEED LIMIT	R2-1	C200 & C201	24"	30"	10.00		25.0			
DO NOT ENTER	R5-1	C200 & C201	30"	30"	6.25		12.5			
WRONG WAY	R5-1a	C200 & C201	36"	36"	18.00		13.0			
STREET NAME	D3-1a	C202	72"	18"		18.00				2
GEOGRAPHIC FEATURE	I-3	C202	30"	36"	15.00					2
DIRECTIONAL ARROW	M6-1	C202	30"	21"	8.75					2

RIGHT OF WAY MARKERS

STATION	OFFSET		REMARKS
	LEFT	RIGHT	
8+46.02	145'		
9+85.78	194'		
15+57.37	229'		
17+83.55	282'		
22+37.76	170'		
24+48.53	57'		
25+68.40	50'		
27+63.15	160'		
30+77.62	200'		
32+47.16	60'		
32+78.98	16'		
8+56.50		50'	
11+53.23		47'	
14+85.05		45'	
17+70.91		16'	
18+99.46		20'	
20+92.01		16'	
21+16.68		27'	
22+40.74		132'	
22+87.71		132'	
24+50.14		35'	
25+19.41		35'	
26+06.45		50'	
27+81.86		125'	
28+02.49		125'	
29+26.87		85'	
30+16.06		55'	
30+99.37		123'	
31+14.49		218'	
31+14.16		285'	
31+43.24		285'	
31+44.94		218'	
31+29.47		120'	
32+18.47		97'	
32+78.98		20'	
33+07.36		22'	