



OVERALL FIRE ALARM BASEMENT PLAN
 FA-501 SCALE: 1" = 20'-0"

GENERAL NOTES:

1. PROVIDE CONTROL MODULES AS NEEDED FOR SPEAKER CONTROL.
2. FIRE ALARM PANEL, DEVICES, WIRE AND COMPONENTS SHALL BE PROVIDED BY THE FIRE ALARM CONTRACTOR. ALL CONDUITS AND JUNCTION BOXES ETC. SHALL BE PROVIDED BY THE ELECTRICAL CONTRACTOR. SEE DRAWING E-301.2 FOR ADDITIONAL INFORMATION.
3. SEE DRAWING A-003 FOR OVERALL RESTROOM ARRANGEMENT AND CONSTRUCTION SEQUENCE.

F-X CODED NOTES NEW FIRE ALARM:

1. PROVIDE COMPUTER, MONITOR AND OTHER DEVICES FOR FRONT END GRAPHICS INTERFACE SYSTEM FOR THE NEW FIRE ALARM SYSTEM.
2. PROVIDE CONTROL MODULES FOR OPERATION OF NAC CIRCUITS NEEDED.
3. PROVIDE MONITOR MODULE FOR NEW FACP AND EXISTING EST PANEL TO MONITOR FIRE ALARM CONDITIONS ON BOTH NEW AND EXISTING PANEL.
4. PROVIDE ANNUNCIATOR CONNECTED TO THE NEW FACP IN THE SECURITY AREA. COORDINATE LOCATION WITH OWNER/USER.

FIRE ALARM SYMBOLS:

- CONTROL MODULE
- MONITOR MODULE
- MONITOR MODULE FOR EXISTING SYSTEM
- NOTIFICATION APPLIANCE CIRCUIT PANEL
- FIRE ALARM CONTROL PANEL
- GRAPHIC COMMAND CENTER
- PHOTOELECTRIC SMOKE DETECTOR

WEST VIRGINIA GENERAL SERVICES DIVISION
 1000 West Virginia State Capitol
 Charleston, West Virginia 25313
 Phone: (304) 784-5421
 Fax: (304) 784-5422
Baker
 Michael Baker Jr., Inc.

REV	DESCRIPTION	DATE	BY	CHK

Designed by: AFW	Date: 3/21/12	Rev:
Drawn by: JAC	Project No: 117579	Project Code: -
Reviewed by:	File name: 3/21/12	Plot scale: 1"=20'-0"
Submitted by: RLB		

WEST VIRGINIA STATE CAPITOL
 CAPITOL RESTROOMS
 RENOVATIONS/RESTORATIONS

OVERALL BASEMENT
 FIRE ALARM PLAN

Sheet reference number:
FA-501