

25. Q: Over-Excavation has a unit of Square Yard (SY). When performing over-excavation it is usually based on cubic yards (CY). Are we to assume a 1 foot depth when figuring this item?

a. *The item includes 18 inches of excavation, heavy duty biaxial geogrid and 18 inches of AASHTO No. 1 stone as backfill.*

26. Q: Please confirm that the height for the conference room partitions is 16'0". Please confirm that the height for the classroom partitions is 12'0".

a. Yes.

27. Q: There are no horizontals shown in the foundation wall – Detail 1 on S1.1.

a. *The horizontal reinforcing will be #4 bars at 12 inches on center typical.*

28. Q: Sound absorbing wall units are not shown.

a. *There are no sound absorbing wall units.*

29. Q: Do the base bid items (#29, 20, 21, 22, 56, 58, 63, 70) for the alternates have to have the same unit cost values as in the base bid?

a. *Contractor should place their own value from their estimator in those line items. We cannot advise or instruct bidders on how to bid the project.*